



PLAN

NOTES:

1. THE CONTRACTOR SHALL NOT OPERATE ANY VALVES OR METERS OWNED BY THE CITY OF HOLLISTER. 72 HOURS NOTICE SHALL BE GIVEN TO THE UTILITY DIVISION FOR THE OPERATION OF THE VALVES.
2. UPON APPROVAL OF THE PUBLIC WORKS INSPECTOR OF THE NEW WATER SYSTEM, THE CONTRACTOR SHALL REMOVE THE BYPASS LINE AND STEEL PLATE, THEN SHUT-OFF VALVES AND INSTALL STEEL PLATES IN THE PRESENCE OF PUBLIC WORKS INSPECTOR.
3. THE DOUBLE CHECK VALVE ASSEMBLY SHALL BE PER STANDARD PLAN B-4-1.
4. SHUT-OFF BOTH VALVES ON THE DOUBLE CHECK VALVE ASSEMBLY DURING PRESSURE TESTING AND DISINFECTION OF THE NEW WATER MAIN.
5. SIZE OF BYPASS MAY BE INCREASED AS DIRECTED BY CITY ENGINEER.
6. BACKFLOW PREVENTION DEVICE SHALL BE LOCATED OUT OF THE RIGHT OF WAY.
7. PERFORM PRESSURE TEST AND BACTERIOLOGICAL TEST PRIOR TO REMOVAL OF BYPASS CONNECTION ACCESSORIES.
8. REMOVE CORPORATION STOP AFTER TESTING AND PLUG WITH STEEL PLATES.

TITLE: BYPASS CONNECTIONS TO NEW WATER MAINS			
DRAWN BY: STAFF	SCALE: NONE	APPROVED:	
REVIEWED BY: DANNY HILLSTOCK	REVISED: OCTOBER, 2019		
CITY OF HOLLISTER ENGINEERING DEPARTMENT		CITY ENGINEER: DANNY HILLSTOCK LIC. NO. 70647	DATE: 11-5-19
STANDARD PLAN			B-11
SHEET 1 OF 1			